

**August 13, 2013**

**ADDENDUM #1**

**13-126 St Charles County Parks Asphalt Trail Paving Project**

Addendum #1 is being issued to address/clarify the Asphalt compaction requirements for this project as follows:

Asphalt compaction shall meet the standard as detailed in the St. Charles County Highway Standards - Section 401.12 as follows;

“Rolling shall begin after spreading the mixture as soon as it will bear the weight of the roller without undue displacement. All rollers shall be in satisfactory condition capable of reversing without backlash, and steel rollers shall be equipped with scrapers. Rollers shall have a system for moistening each roll or wheel. The compacted mixture shall have a density of not less than 98.0 percent of that obtained by the laboratory compaction of a specimen made in the proportions of the approved mixture. Density will be determined by the direct transmission nuclear method in accordance with MoDOT Test Method T41 or by specific gravity method.”

---

Bidders shall sign this Addendum as acknowledgment and return it with the bid.

**BID ADDENDUM**

**Addendum #1**

**Dated** \_\_\_\_\_

We, the undersigned, acknowledge the receipt of the above addendum(s) as dated.

By: \_\_\_\_\_

Title: \_\_\_\_\_

Company: \_\_\_\_\_

Date: \_\_\_\_\_