

This road project paid in part through the
St. Charles County ½ Cent Transportation Sales Tax.

WESTWOOD DRIVE

Project Location:

Westwood Drive from South Breeze Lane to Highway 94

Project Description:

This project involved improvements to an existing 2-lane roadway that was originally an old road that had been upgraded over the years with asphalt overlays. The roadway consisted of narrow lanes with no shoulders and ditches adjacent to the travel lanes causing dangerous drop-off conditions. Therefore, this project involved reconstructing the pavement to provide for 12-foot-wide lanes with curb and gutter. The project also provided for dedicated left turn lanes at the intersections of Emerald Place Drive and Motherhead Road. To accommodate pedestrians, sidewalks were added along the north side of road allowing for connections to be made to existing facilities along some of the intersecting roadways along Westwood Drive.

Project Status: Construction completed

Original Project Funding:

TOTAL	County	Sponsor	Federal	Other
\$5,150,500	\$4,345,000	\$0	\$805,500	\$0

Final Project Total: \$3,887,470

Final County Contribution: \$3,081,970

Completion Year: 2020

Contact: County Highway

Phone: 636-949-7305

Email: highway@sccmo.org

Website: www.sccmo.org/233/Highway

Update: 6/8/2022



WESTWOOD DRIVE

S. BREEZE LN

EMERALD PLACE DR

MOTHERHEAD RD

GIMMARON DR

HIGHWAY 94



WESTWOOD DRIVE
FROM S. BREEZE LN
TO HIGHWAY 94
PROJECT LENGTH: 1.21 MILES

